## SCOPE OF WORK

FLOOR PROTECTION

**CLEAN UP** 

HAUL TRASH

**PERMIT** 

**DRAWINGS** 

DEMO - REMOVE TOILET, SHOWER UNIT, FAUCET, VANITY, TOP FLOORING, DOOR

FRAME IN POCKET DOOR INCLUDING POCKET DOOR FRAME & POCKET DOOR

JACK HAMMER & REMOVE

PLUMBIMG ROUGH IN – MOVE TOILET, SHOWER DRAIN, LAVATORY WATER & DRAIN

**RE-POUR CONCRETE** 

**ROUGH IN ELECTRIC** 

**INSTALL VENT FAN** 

INSTALL LEVEL SHOWER FLOOR SYSTEM

INSTALL BLOCKING IN WALLS

**DUROCK WALLS** 

WATER PROOF WALLS & FLOOR

TILE FLOOR

TILE WALLS

**INSTALL VANITY CABINET** 

**INSTALL TOP** 

FINAL PLUMBING

FINAL ELECTRIC

**BATHROOM FLOORING** 

TRIM OUT POCKET DOOR

**INSTALL BASE BOARD** 

INSTALL QUARTER ROUND

**CAULK & PUTTY TRIM** 

PRIME WALLS AND TRIM

PAINT CEILING

PAINT WALLS

PAINT TRIM

FINAL CLEANING

