State Route - 29 Rehabilitation and Complete Street Newsletter

Issue 12 - November 25, 2026

Solano Public Information, Sabrina Martinez here to give you an update on the latest activities on State Route 29 (SR-29) - also known as Sonoma Boulevard in Vallejo. The last month included the final paving, a major milestone for the project. Caltrans would like to thank the community for being patient with the crews as they finished the paving operation in the daytime. Paving can get tricky when the temperatures start to drop.

There have been a few changes to the coming operations due to weather and rain. Crews had hoped to get started on striping in late November. However, due to the weather, this has pushed the final striping to start on or around, Dec. 7. Temperatures need to be 50 degrees or above and no rain for two days for a completely dry pavement.



These same conditions are needed to put down temporary striping, so floppies and other measures have been made to make it safe for motorists until the conditions needed are met.

What makes this special? It is not a tape or paint used for striping, but a thermal plastic. It adheres to the asphalt and is highly reflective for more visibility in the day and night. It has a higher durability of approximately five to eight years versus standard striping of just six months to two years - which means less maintenance costs and higher durability for high traffic areas.

During this work motorist should expect and prepare for delays. Know your altternate routes, begin with using Caltrans Quickmap.

Continued work includes median work, installation of bike racks, benches and landscape. Finalizing the prograing of new lighting on the route and anticipated permemant striping.

This Caltrans Newsletter for State Route 29 will be distributed on a monthly basis.
Sign Up to Stay Updated
CONTACT:
Caltrans Public Information Officers for Solano County
Sabrina Martinez | sabrina.martinez@dot.ca.gov



© 2026 California Department of Transportation