



www.mwaeng.com

Mainelli Wagner & Associates, Inc.

6920 Van Dorn Street, Lincoln, NE 68506 Phone: (402) 421-1717 Fax: (402) 421-6061

August 26, 2026


The Platte County Board of Supervisors will be receiving sealed bids for the project enclosed. Sealed bids will be received by the Platte County Clerk's office until 10:00 am on September 17, 2026, and will be opened shortly thereafter. The Bids will be presented to the Board of Supervisors for consideration at the regularly scheduled board meeting on September 22, 2026.

If you have any questions regarding this project or the enclosed information, please contact Mainelli Wagner & Associates, Inc. prior to the Bid Letting.

Adam Mace, P.E.
Mainelli Wagner & Associates, Inc.
6920 Van Dorn Street
Lincoln, NE 68506
Phone: 402-421-1717

Mainelli Wagner & Associates, Inc.

Adam Mace, P.E.



Not to be used for Bid

Mainelli Wagner & Associates, Inc.
6920 Van Dorn Street
Lincoln, NE 68506
Office: 402-421-1717
Nebraska C.O.A. CA-1137

BID DOCUMENTS AND SPECIFICATIONS

Monastery Road Phase 1 – C-71(907), C-71(908), C-71(909), C-71(913), & C-71(915)

**Creston South, C-71(907) & C-71(915)
Structure No. C007105135**

**Creston Southeast, C-71(908) & C-71(913)
Structure No. C007105140**

**Creston East, C-71(909)
Structure No. C007105145**

**All Sites are Located on Monastery Road between 385 Street and 490 Street in
Platte County, Nebraska**

Monastery Road - Future Phases

Platte County intends to replace structures on Monastery Road between 280th and 325th Streets (Phase 2) and between 325th and 385th Streets (Phase 3). Phases 2 and 3 are anticipated to be let for construction by the end of 2026.

Utility relocation is anticipated to begin in 2027, extending from 280th Street to 490th Street, in preparation for future grading and concrete pavement improvements along the entire 14-mile Monastery Road corridor.

Future phases and improvements are anticipated only and are not guaranteed to occur. Project schedules, phasing, and construction plans are subject to change based on funding, approvals, priorities, and other factors.

Not to be used for Bid

NOTICE TO BIDDERS

Platte County Board of Supervisors will be receiving sealed bids for the projects enclosed. Sealed bids will be received at the office of the Platte County Clerk's Office until September 17, 2026, at 10:00 a.m. and opened shortly thereafter, for the construction of four concrete box culverts, one 100' three-span continuous concrete slab bridge, twenty roadway culverts with concrete headwalls, roadway grading, asphaltic concrete pavement, and other related incidental work. The bids will be presented to the Board of Supervisors for consideration on September 22, 2026, at their regularly scheduled meeting. The project sites C-71(907), C-71(908), C-71(909), C-71(913), C-71(915), & all the roadway culvert pipes are located on Monastery Road between 385 Street and 490 Street, all in Platte County, Nebraska.

The project is referred to as "Monastery Road Phase 1 – C-71(907), C-71(908), C-71(909), C-71(913), & C-71(915)" and shall include all labor, materials, transportation and equipment required for the construction of: C-71(907) – three-span 100'-0" continuous concrete slab bridge on a 0-deg. skew with a 40 ft. clear roadway, C-71(908) – triple 12' x 8' x 65' concrete box culvert on a 0-deg. skew with paved outlet apron, C-71(909) – twin 12' x 7' x 64' concrete box culvert on a 0-deg. skew with paved outlet apron, C-71(913) – single 10' x 6' x 74' concrete box culvert on a 15-deg. skew (lhb), C-71(915) – single 8' x 8' x 160' double broken back concrete box culvert on a 0-deg. skew with paved outlet apron, Roadway Culvert Pipes – 5 sites-24", 2 sites-30", 7 sites-36", 3 sites-42", 1 site-54", 1 site-60", and 1 site-72", all corrugated metal pipes with concrete headwalls at inlet and outlet, most sites with two elbows; all structures with pavement removal, subgrade preparation, 8" asphaltic concrete pavement, earth shoulder construction, and other incidental work

Copies of the Bid Documents and Specifications are open to public inspection at the office of the Platte County Highway Department, 2610 14th St. Columbus, NE 68601. A digital set of bid documents may be obtained from Mainelli Wagner & Associates, Inc. for a non-refundable fee of \$100.00. An optional half-sized paper set of the bid documents is available for a non-refundable fee of \$225.00 (6920 Van Dorn St., Lincoln, Nebraska 68506; PH: 402-421-1717). All Bid Proposals must be submitted on the forms furnished with the Bid Documents.

The sealed bids may be mailed or delivered to the Platte County Clerk, 2610 14th St., Columbus, NE 68601, and should be plainly marked as, "Construction Bid Proposal – Monastery Road Phase 1 – C-71(907), C-71(908), C-71(909), C-71(913), & C-71(915)".

Along with its Bid Proposal, each bidder shall submit an unconditional Bid Bond or Certified Check made payable to the County Treasurer of Platte County, Nebraska, in an amount equal to five (5) percent of the Bid Proposal. Also, each bidder is to include an estimated start of construction and completion date with their Bid Proposal. The desired completion date is August 1, 2027. The successful bidder (i.e., Contractor) will be allowed two hundred and fifty (250) calendar days for completion of all the sites after beginning work on the project, provided they do not exceed their specified completion date. Additional days due to weather may be granted at the discretion of the Engineer. No site can be started without the intent to complete that site without delay from the other sites; therefore, the Contractor will not be allowed to start the removals at a site unless they have committed a crew to complete the work at that site. Contractor to maintain local access to landowners at all times.

Within ten (10) days following the award of the Contract, the successful bidder shall furnish a surety bond or bonds in an amount equal to or greater than the full amount of the contract. The surety and form of the bonds are subject to acceptance by the Platte County Board of Supervisors.

The Platte County Board of Supervisors reserves the right to reject any and all bids or to waive any irregularities in bids received. Award of the Contract will be in accordance with the County Purchasing Act's competitive bidding considerations as set forth in Neb.Rev.Stat. §§ 23-3110 to 23-3114. Platte County is an Equal Opportunity Employer.

Platte County Clerk

Not to be used for Bid

PROPOSAL FOR: PLATTE COUNTY MONASTERY ROAD PHASE 1 –
C-71(907), C-71(908), C-71(909), C-71(913), & C-71(915)
PLATTE COUNTY, NEBRASKA

Board of Supervisors
Platte County Courthouse
Columbus, Nebraska 68601

Platte County Board Members:

_____,(Contractor) after reviewing these Bid Documents and Specifications in full, propose to furnish all labor, transportation, materials and equipment and all other miscellaneous items required to construct the project as shown at the following unit prices:

C-71(907), C007105135: 100'-0" THREE-SPAN CONTINUOUS CONCRETE SLAB BRIDGE
&
C-71(915): SINGLE 8'x8'x160' DOUBLE BROKEN BACK CONCRETE BOX CULVERT
ON A 0 DEG. SKEW WITH A PAVED OUTLET APRON

ITEM NO.	PLAN QUANTITY	ITEM DESCRIPTION	UNITS	UNIT PRICE	AMOUNT
1-1.	1.000	Mobilization	LS	_____	_____
1-2.	1.000	Site Preparation	LS	_____	_____
1-3.	4,330.000	Remove Pavement	SY	_____	_____
1-4.	48,777.000	Earthwork Measured in Embankment	CY	_____	_____
1-5.	80.000	24" Corrugated Metal Drive Pipe	LF	_____	_____
1-6.	353.000	24" Corrugated Metal Pipe	LF	_____	_____
1-7.	218.000	30" Corrugated Metal Pipe	LF	_____	_____
1-8.	501.000	36" Corrugated Metal Pipe	LF	_____	_____
1-9.	498.000	42" Corrugated Metal Pipe	LF	_____	_____
1-10.	92.000	60" Corrugated Metal Pipe	LF	_____	_____
1-11.	129.000	72" Corrugated Metal Pipe	LF	_____	_____
1-12.	42.200	Class 47B-3000 Concrete for Headwall	CY	_____	_____

Not to be used for Bid

1-13.	5,455.000	Reinforcing Steel for Headwall	LB	_____	_____
1-14.	160.000	HP 8 inch x 36 lb Steel Piling	LF	_____	_____
1-15.	625.000	Structural Steel for Headwall	LB	_____	_____
1-16.	65.000	Crushed Rock for Base Course	TON	_____	_____
1-17.	233.700	Class 47B-4000 Concrete for Box Culvert	CY	_____	_____
1-18.	35,344.000	Reinforcing Steel for Box Culvert	LB	_____	_____
1-19.	69.000	Crushed Rock Surface Course	TON	_____	_____
1-20.	1.000	End Anchorage Assembly	EACH	_____	_____
1-21.	4.000	Bridge Approach Section	EACH	_____	_____
1-22.	3.000	Guardrail End Treatment, Type II	EACH	_____	_____
1-23.	112.500	W-Beam Guardrail	LF	_____	_____
1-24.	3,931.000	Subgrade Preparation	SY	_____	_____
1-25.	89.000	Water	MGAL	_____	_____
1-26.	1,745.000	Asphaltic Concrete, Type SPR	TON	_____	_____
1-27.	29.480	Earth Shoulder Construction	STA	_____	_____
1-28.	4,638.000	Permanent Pavement Marking, Paint	LF	_____	_____
1-29.	29.380	Covercrop Seeding	ACRE	_____	_____
1-30.	28.500	Seeding, Type A	ACRE	_____	_____
1-31.	4,255.000	Erosion Control, Class 1D	SY	_____	_____

Not to be used for Bid

1-32.	312.000	Fabric Silt Fence, Low Porosity	LF	_____	_____
1-33.	420.000	Fabric Silt Fence, High Porosity	LF	_____	_____
1-34.	1.000	Access Crossing at Sta. 447+50	LS	_____	_____
1-35.	1.000	Access Crossing at Sta. 507+95	LS	_____	_____
1-36.	1,900.000	Temporary Silt Fence	LF	_____	_____
1-37.	1.000	Traffic Control	LS	_____	_____
1-38.	1.000	Abutment No. 1 Excavation	LS	_____	_____
1-39.	1.000	Bent No. 1 Excavation	LS	_____	_____
1-40.	1.000	Bent No. 2 Excavation	LS	_____	_____
1-41.	1.000	Abutment No. 2 Excavation	LS	_____	_____
1-42.	260.800	Class 47B-3000 Concrete for Bridge	CY	_____	_____
1-43.	242.600	Class 47BD-4000 Concrete for Bridge	CY	_____	_____
1-44.	74,782.000	Epoxy Coated Reinforcing Steel	LB	_____	_____
1-45.	30,593.000	Epoxy Coated Reinforcing Steel for Pavement Approaches	LB	_____	_____
1-46.	176.700	Concrete for Pavement Approaches Class 47BD-4000	CY	_____	_____
1-47.	2,860.000	Structural Steel for Substructure	LB	_____	_____
1-48.	410.000	HP 12 inch x 53 lb Steel Test Piling	LF	_____	_____
1-49.	5,040.000	HP 12 inch x 53 lb Steel Piling	LF	_____	_____

Not to be used for Bid

1-50.	3,630.000	Steel Sheet Piling	SF	_____	_____
1-51.	80.000	Preformed Expansion Joint, Type B	LF	_____	_____
1-52.	465.000	Granular Backfill	CY	_____	_____

TOTAL FOR C-71(907) & C-71(915), (T1)

C-71(908), C007105140: TRIPLE 12'x8'x65' CONCRETE BOX CULVERT ON A 0 DEG.
SKEW WITH A PAVED OUTLET APRON &

C-71(913): SINGLE 10'x6'x74' CONCRETE BOX CULVERT ON A 15 DEG. SKEW (LHB)

ITEM NO.	PLAN QUANTITY	ITEM DESCRIPTION	UNITS	UNIT PRICE	AMOUNT
2-1.	1.000	Mobilization	LS	_____	_____
2-2.	1.000	Site Preparation	LS	_____	_____
2-3.	875.000	Remove Pavement	SY	_____	_____
2-4.	8,689.000	Earthwork Measured in Embankment	CY	_____	_____
2-5.	114.000	24" Corrugated Metal Pipe	LF	_____	_____
2-6.	176.000	54" Corrugated Metal Pipe	LF	_____	_____
2-7.	6.200	Class 47B-3000 Concrete for Headwall	CY	_____	_____
2-8.	734.000	Reinforcing Steel for Headwall	LB	_____	_____
2-9.	125.000	Crushed Rock for Base Course	TON	_____	_____
2-10.	376.600	Class 47B-4000 Concrete for Box Culvert	CY	_____	_____
2-11.	59,515.000	Reinforcing Steel for Box Culvert	LB	_____	_____
2-12.	80.000	HP 8 inch x 36 lb Steel Piling	LF	_____	_____
2-13.	299.000	Structural Steel for Headwall	LB	_____	_____

Not to be used for Bid

2-14.	968.000	Subgrade Preparation	SY	_____	_____
2-15.	17.000	Water	MGAL	_____	_____
2-16.	430.000	Asphaltic Concrete, Type SPR	TON	_____	_____
2-17.	7.260	Earth Shoulder Construction	STA	_____	_____
2-18.	1,067.000	Permanent Pavement Marking, Paint	LF	_____	_____
2-19.	2.250	Covercrop Seeding	ACRE	_____	_____
2-20.	2.250	Seeding, Type A	ACRE	_____	_____
2-21.	201.000	Fabric Silt Fence, Low Porosity	LF	_____	_____
2-22.	60.000	Fabric Silt Fence, High Porosity	LF	_____	_____
2-23.	1.000	Access Crossing at Sta. 697+60	LS	_____	_____
2-24.	1.000	Access Crossing at Sta. 708+40	LS	_____	_____
2-25.	300.000	Temporary Silt Fence	LF	_____	_____
2-26.	1.000	Traffic Control	LS	_____	_____

TOTAL FOR C-71(908) & C-71(913), (T2) _____

C-71(909), C007105145: TWIN 12'x7'x64' CONCRETE BOX CULVERT ON A 0 DEG.
SKEW WITH A PAVED OUTLET APRON

ITEM NO.	PLAN QUANTITY	ITEM DESCRIPTION	UNITS	UNIT PRICE	AMOUNT
3-1.	1.000	Mobilization	LS	_____	_____
3-2.	1.000	Site Preparation	LS	_____	_____
3-3.	583.000	Remove Pavement	SY	_____	_____
3-4.	4,441.000	Earthwork Measured in Embankment	CY	_____	_____

Not to be used for Bid

3-5.	177.000	36" Corrugated Metal Pipe	LF	_____	_____
3-6.	4.800	Class 47B-3000 Concrete for Headwall	CY	_____	_____
3-7.	740.000	Reinforcing Steel for Headwall	LB	_____	_____
3-8.	62.000	Crushed Rock for Base Course	TON	_____	_____
3-9.	198.000	Class 47B-4000 Concrete for Box Culvert	CY	_____	_____
3-10.	30,404.000	Reinforcing Steel for Box Culvert	LB	_____	_____
3-11.	581.000	Subgrade Preparation	SY	_____	_____
3-12.	10.000	Water	MGAL	_____	_____
3-13.	259.000	Asphaltic Concrete, Type SPR	TON	_____	_____
3-14.	4.360	Earth Shoulder Construction	STA	_____	_____
3-15.	625.000	Permanent Pavement Marking, Paint	LF	_____	_____
3-16.	1.500	Covercrop Seeding	ACRE	_____	_____
3-17.	1.500	Seeding, Type A	ACRE	_____	_____
3-18.	94.000	Fabric Silt Fence, Low Porosity	LF	_____	_____
3-19.	60.000	Fabric Silt Fence, High Porosity	LF	_____	_____
3-20.	1.000	Access Crossing	LS	_____	_____
3-21.	300.000	Temporary Silt Fence	LF	_____	_____
3-22.	1.000	Traffic Control	LS	_____	_____
TOTAL FOR C-71(909), (T3)				_____	_____

Not to be used for Bid

TOTAL FOR PROJECT (T1+T2+T3)

The Contract will be awarded based on the TOTAL FOR PROJECT, in conjunction with the Nebraska County Purchasing Act. The County reserves the right to remove or adjust any pay item.

We understand that this will be a lump sum contract and the total contract amount will be obtained by multiplying the Plan Quantities by the associated Unit Prices.

If awarded the contract, we will furnish a surety bond and certificates of insurance as indicated in the Contract Documents.

As specified in the Notice to Bidders, we hereby submit this BID BOND CERTIFIED CHECK in the amount of \$ _____ (5% of total bid). This bond will become the property of Platte County if an award is offered within thirty (30) days after the bid opening and we, as the successful bidder, fail to enter into a contract with Platte County.

The Undersigned agrees to correct any failures resulting from faulty work appearing within TWELVE (12) MONTHS after final payment.

C-71(907), C-71(908), C-71(909), C-71(913), & C-71(915) Construction Schedule:

Start of Construction Date: _____

End of Construction Date: _____

Respectfully Submitted,

(Signature)

(Printed Name)

(Title)

(Company)

(Address)

(Phone)

(E-Mail)

Not to be used for Bid