



Pro Reno Group is looking for sub-contractors to erect metal canopies. This contract has been in place since March 2019 and is on-going between PRG and General Contractor until told otherwise.

SCOPE OF WORK CFA CANOPY

Erection of drive thru canopies – attached or detached to building
Blueprints are sent with materials and training provided as needed/requested

General type of work expected:

Steel columns that hold canopy off the ground are installed and bolted to concrete footers with 1 ½" all threads and nuts and tightened down with hammer wrenches are installed with the forklift, held by lifting straps rated for columns. All lifts have tag lines installed with spotters. Iron headers are then placed on top with forklift, tag lines, and bolted in with ¾" bolts, lock washer, and nuts. Once everything is bolted in place, thin gauge steel deck pans are lifted (with the help of the scissor lift) and bolted into place on the bottom side of the iron headers.

After all deck pans are in place and secured, white trim and fascia installed along the perimeter of the canopy. Light weight lifted by hand and installed with small screws. Install gutters on bottom of deck pans secure with self-tapping screws. Everything is caulked in - to ensure weatherproofing.

Examples below:



Skills Required

Small Steel Erector Experience/Metal Installation

Work experience with sheet metal a plus, team environment, outdoor, day and night work (dependent on site), and off the ground environment. Willing to travel 80-90% - in/out of state if it demands. Measurement skills a must. No welding required. General knowledge of construction sites and safety, tools and tensioning bolts, rigging a plus, boom lifts/scissor lifts cert a plus. Looking for individuals or crews. Insured, Reliable, Professional

For more information, contact Pro Reno Group, LLC at 817-682-6685 www.prorenogroup.com