



New Orleans Education League
 2424 N. Arnoult Rd.
 Metairie, LA 70001
 (504) 837-2700
 www.hbanoel.org

Site: W. Catawba Dr., Harvey **90 Day Timeframe** Company Name: _____

BIDDERS ARE RESPONSIBLE FOR THEIR OWN MEASUREMENTS. INACCURATE BIDS RESULTING FROM INACCURATE MEASUREMENTS ARE THE FAULT OF THE BIDDING CONTRACTOR.

Exterior:	Bid Amount
1. R&R exterior door – metal – insulated – flush or panel style. Side door	
2. Prime and paint door unit	
3. Install door lockset and deadbolt – exterior	
4. Remove approx. 1,566 SF of siding – hardboard – lap pattern – 12” existing	
5. R&R approx. 1,566 SF of house wrap (air/moisture barrier)	
6. Install approx. 1,566 fiber cement lap siding – 12”	
7. Remove approx. 1,154 SF builder board – ½” (composition or fiberboard sheathing) existing up to 8ft high	
8. Install approx. 1,154 sheathing – plywood – ½” CDX up to 8ft high	
9. R&R approx. 850 SF of sheathing – plywood – 5/8” CDX. Roof decking	
10. Seal and paint approx. 1,566 of siding. Prime. 2 coats	
11. Remove approximately 31sq furnish and install approximately 36sq of composite 25 year roofing including felt and nails as needed. Replace all stacks and jacks. Install proper drip edge.	
12. Roof should be installed according to manufacturer guidelines and adhere to all appropriate parish codes.	
13. R&R approx. 59 LF fascia – 1” x 8” - #2 pine	
14. R&R approx. 8 LF of fascia – 2” x 6”	
15. Prime and paint approx. 67 LF of fascia – wood – 6” – 8” wide. 2 coats	
16. R&R approx. 65 SF soffit – wood	
17. Prime and paint exterior soffit – wood	
18. Remove storage shed – metal. Existing attached to home.	
Total Bid:	

LIVING ROOM:	Bid Amount
19. Remove 2 aluminum windows, single hung 13-19 sf. Existing	
20. Install 2 new Vinyl windows, single hung, 13-19 sf	
21. R&R window trim set (casing and stop)	
22. Seal and paint trim. 2 coats.	
Total Bid:	



New Orleans Education League
 2424 N. Arnoult Rd.
 Metairie, LA 70001
 (504) 837-2700
 www.hbanoel.org

Site: W. Catawba Dr., Harvey **90 Day Timeframe** Company Name: _____

LIVING ROOM 2:	Bid Amount
23. Remove aluminum window, single hung 13-19 sf. Existing	
24. Install new vinyl window, single hung 13-19 sf	
25. R&R window trim set (casing & stop)	
26. Seal and paint trim. 2 coats	
Total Bid:	

KITCHEN:	
27. Remove aluminum window, single hung 13-19 sf. Existing	
28. Install new vinyl window, single hung 13-19 sf	
29. R&R window trim set (casing & stop)	
30. Seal and paint trim. 2 coats	
Total Bid:	

LAUNDRY ROOM:	
31. R&R approx. 64 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. Ceiling	
32. Seal, prime, and paint the surface area. 2 coats	
33. R&R light fixture. Similar type.	
Total:	

BEDROOM 1:	
34. Remove aluminum window, single hung 13-19 sf. Existing	
35. Install new vinyl window, single hung 13-19 sf	
36. R&R window trim set (casing & stop)	
37. Seal and paint trim. 2 coats	
Total:	

Site: W. Catawba Dr., Harvey **90 Day Timeframe** Company Name: _____

BEDROOM 2:	
38. Remove aluminum window, single hung 13-19 sf. Existing	
39. Install new vinyl window, single hung 13-19 sf	
40. R&R approx. 140 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. Ceiling	
41. Seal, prime, and paint the surface area. 2 coats	
42. R&R ceiling fan and light	
43. R&R heat/AC register – mechanically attached	
Total:	

BEDROOM 3:	
44. R&R approx. 264 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. Ceiling	
45. Seal, prime, and paint the surface area. 2 coats	
46. R&R ceiling fan and light	
47. R&R heat/AC register – mechanically attached	
Total:	

BEDROOM 4:	
48. R&R approx. 34 LF casing – 2 1/4". Closet door	
49. Paint casing. 2 coats	
50. Remove 2 aluminum windows, single hung 13-19 sf. Existing	
51. Install 2 new vinyl windows, single hung 13-19 sf	
52. R&R window trim set (casing & stop)	
53. Seal and paint trim. 2 coats	
54. R&R approx. 14 LF of baseboard – 4 1/4". CLOSET ONLY.	
55. Seal and paint baseboards. 2 coats	
56. R&R approx. 112 SF of 1/2" drywall. Hung, taped, floated, ready for paint. Closet walls.	
57. Seal, prime, paint surface area. 3 coats.	
58. R&R approx. 177 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. Ceiling	
59. Seal, prime, and paint the surface area. 2 coats	
60. R&R ceiling fan and light	
61. R&R heat/ac register – mechanically attached	
Total:	



New Orleans Education League
2424 N. Arnoult Rd.
Metairie, LA 70001
(504) 837-2700
www.hbanoel.org

Site: W. Catawba Dr., Harvey **90 Day Timeframe** Company Name: _____

BATHROOM 1:	
62. R&R approx. 53 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. Ceiling	
63. Seal, prime, and paint the surface area. 2 coats	
64. Remove light fixture and abandon existing opening.	
Total:	

BATHROOM 2:	
65. R&R approx. 66 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. Ceiling	
66. Seal, prime, and paint the surface area. 2 coats	
67. Remove light fixture and abandon existing opening	
Total:	

This job will be completed within 90 days of contract signing.

Company Representative Signature: _____ Total Bid: _____

Company Representative Name: _____ Date: _____