



New Orleans Education League
 2424 N. Arnoult Rd.
 Metairie, LA 70001
 (504) 837-2700
 www.hbanoel.org

Site: Carol Sue Ave., Gretna **60 Day Timeframe** Company Name: _____

BIDDERS ARE RESPONSIBLE FOR THEIR OWN MEASUREMENTS. INACCURATE BIDS RESULTING FROM INACCURATE MEASUREMENTS ARE THE FAULT OF THE BIDDING CONTRACTOR.

EXTERIOR:	Bid Amount
1. R&R exterior door – metal – insulated/wood – high grade (Front and Back Doors)	
2. R&R exterior door sidelite – pre-attached – high grade	
3. Door lockset & Deadbolt – exterior – high grade	
4. R&R exterior door – metal – insulated – flush or panel style (back and side door)	
5. Door lockset & deadbolt – exterior	
6. Prime and paint door unit – exterior (include all new doors)	
7. Prime and paint door sidelite – exterior (per side)	
8. Remove approximately 38sq furnish and install approximately 44sq of composite 25 year roofing including felt and nails as needed. Replace all stacks and jacks. Install proper drip edge.	
9. Roof should be installed according to manufacturer guidelines and adhere to all appropriate parish codes.	
10. R&R approx. 110 LF of fascia 1" x 10"	
11. Prime and paint exterior fascia - wood	
12. R&R approx. 165 SF of soffit – wood	
13. Prime and paint exterior soffit - wood	
Total:	

DEN:	Bid Amount
14. R&R approximately 672 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
15. Seal, Prime, Paint approximately 672 SF of surface area (2 coats)	
16. Detach and reset recessed light	
17. Detach and reset light fixture	
Total Bid:	



New Orleans Education League
 2424 N. Arnoult Rd.
 Metairie, LA 70001
 (504) 837-2700
 www.hbanoel.org

Site: Carol Sue Ave., Gretna **60 Day Timeframe** Company Name: _____

2nd FLOOR HALLWAY:	Bid Amount
18. R&R approximately 168 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
19. R&R approximately 168 SF of batt insulation – 6" – R19 – paper faced	
20. Seal, Prime, Paint approximately 168 SF of surface area (2 coats)	
21. Detach and reset light fixture	
Total Bid:	

BEDROOM 1:	
22. R&R approximately 168 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
23. R&R approximately 168 SF of batt insulation – 6" – R19 – paper faced	
24. Seal, Prime, Paint approximately 168 SF of surface area (2 coats)	
25. R&R approx. 280 SF of ½" drywall – hung, taped, floated, ready for paint WALLS	
26. Seal, prime, paint (twice) approx. 600 SF of surface area (3 coats) paint all walls	
27. R&R approx. 15 LF of baseboards 4 ¼"	
28. Seal and paint baseboards – 2 coast	
29. Detach and reset light fixtures	
Total Bid:	

BEDROOM 2:	
30. Remove 2 aluminum window, single hung 9-12 SF. Existing	
31. Replace 2 vinyl window, single hung, 9-12 SF – high grade	
32. Replace 2 vinyl window – half round, 24" wide. Install new	
33. R&R approximately 144 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
34. R&R approximately 144 SF of batt insulation – 6" – R19 – paper faced	
35. Seal, Prime, Paint approximately 144 SF of surface area (2 coats)	
36. Detach and reset ceiling fan and light	
Total:	

This job will be completed within 60 days of contract signing.

Company Representative Signature: _____ Total Bid: _____

Company Representative Name: _____ Date: _____