



New Orleans Education League
 2424 N. Arnoult Rd.
 Metairie, LA 70001
 (504) 837-2700
 www.hbanoel.org

Site: (B) Coretta Dr., Avondale **60 Day Timeframe** Company Name: _____

BIDDERS ARE RESPONSIBLE FOR THEIR OWN MEASUREMENTS. INACCURATE BIDS RESULTING FROM INACCURATE MEASUREMENTS ARE THE FAULT OF THE BIDDING CONTRACTOR.

EXTERIOR:	Bid Amount
1. R&R exterior doors – fiberglass/wood with detail – premium grade (front and side doors) Colored/pre-hung units	
2. Replace door lockset and deadbolt on exterior doors – standard grade	
3. Remove approximately 18sq furnish and install approximately 22sq of composite 25 year roofing including felt and nails as needed. Replace all stacks and jacks. Install proper drip edge.	
4. Roof should be installed according to manufacturer guidelines and adhere to all appropriate parish codes.	
Total Bid:	

LIVING ROOM:	Bid Amount
5. R&R approximately 200 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
6. Remove approx. 200 SF of blown-in insulation – 8" depth – R19. Existing.	
7. Remove approx. 200 SF of batt insulation – 12" – R38 – paper faced. Install new.	
8. Seal, prime, paint the surface area (2 coats)	
9. Detach and reset light fixture	
Total Bid:	

DINING ROOM:	Bid Amount
10. R&R approximately 80 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
11. Remove approx. 80 SF of blown-in insulation – 8" depth – R19. Existing.	
12. Remove approx. 80 SF of batt insulation – 12" – R38 – paper faced. Install new.	
13. Seal, prime, paint the surface area (2 coats)	
14. Detach and reset light fixture	
Total Bid:	

BEDROOM 1:	
15. Replace window screen, 10-16 SF	
16. R&R approx. 164 SF of carpet	
17. Remove and dispose of approx. 164 SF asbestos floor tile	
18. Remove approx. 164 SF asbestos floor mastic	
Total:	



New Orleans Education League
2424 N. Arnoult Rd.
Metairie, LA 70001
(504) 837-2700
www.hbanoel.org

Site: (B) Coretta Dr., Avondale **60 Day Timeframe** Company Name: _____

KITCHEN:	
19. R&R approximately 104 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
20. Remove approx. 104 SF of blown-in insulation – 8" depth – R19. Existing.	
21. Remove approx. 104 SF of batt insulation – 12" – R38 – paper faced. Install new.	
22. Seal, prime, paint the surface area (2 coats)	
23. Detach and reset light fixture	
Total Bid:	

HALLWAY:	
24. R&R approximately 40 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
25. Remove approx. 40 SF of blown-in insulation – 8" depth – R19. Existing.	
26. Remove approx. 40 SF of batt insulation – 12" – R38 – paper faced. Install new.	
27. Seal, prime, paint the surface area (2 coats)	
28. Detach and reset light fixture	
29. R&R attic entrance cover and trim	
30. Paint attic cover and trim	
Total:	

Bedroom 2:	
31. R&R approximately 35 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
32. Remove approx. 35 SF of blown-in insulation – 8" depth – R19. Existing.	
33. Install approx. 35 SF of batt insulation – 12" – R38 – paper faced. Install new.	
34. Seal, prime, paint the surface area (2 coats)	
35. R&R bathroom ventilation fan, light, and heater	
Total:	

This job will be completed within 60 days of contract signing.

Company Representative Signature: _____ Total Bid: _____

Company Representative Name: _____ Date: _____