



New Orleans Education League  
 2424 N. Arnoult Rd.  
 Metairie, LA 70001  
 (504) 837-2700  
 www.hbanoel.org

Site: Betty Blvd, Marrero **90 Day Timeframe** Company Name: \_\_\_\_\_

**BIDDERS ARE RESPONSIBLE FOR THEIR OWN MEASUREMENTS. INACCURATE BIDS RESULTING FROM INACCURATE MEASUREMENTS ARE THE FAULT OF THE BIDDING CONTRACTOR.**

<b>LIVING ROOM:</b>	Bid Amount
1. R&R approximately 260 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
2. R&R approximately 260 SF of batt insulation – 6" – R19 – paper faced	
3. Seal, Prime, Paint approximately 260 SF of surface area (2 coats)	
4. R&R approximately 50 LF of crown molding – 5 1/4"	
5. Seal & paint approx. 50 LF of crown molding oversized – two coats	
Total Bid:	

<b>DINING ROOM:</b>	Bid Amount
6. R&R Interior door unit	
7. Seal & Paint door, both sides	
8. Door knob – Interior. Reset door knob/lock set	
9. R&R approx. 8 LF of 1/2" drywall up to 2' tall - CLOSET WALLS	
10. Seal, prime, paint approx. 80 SF of surface area (3 coats) all closet walls	
11. R&R approximately 108 SF of drywall – hung, taped, heavy texture, ready for paint. CEILING	
12. R&R approx. 108 SF of batt insulation – 6" – R19 – paper faced	
13. Seal, prime, paint approx. 108 SF the surface area (2 coats)	
14. R&R approx. 22 LF of crown molding – 5 1/4"	
15. Seal, paint approx. 22 LF of crown molding, oversized, 2 coats	
16. R&R approx. 8 LF of baseboard 6"	
17. Seal, paint baseboards. 2 coats	
18. R&R Light fixture. Use similar type.	
Total Bid:	

<b>KITCHEN:</b>	Bid Amount
19. R&R approx. 64 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
20. R&R approx. 64 SF of batt insulation - 6" – R19 – paper faced	
21. Seal, Prime, Paint approximately 64 SF of surface area (2 coats)	
22. Detach and reset approx. 22 LF of crown molding – 4 1/4"	
23. Seal and paint approx. 22 LF of crown molding – two coats	
24. R&R light fixture. Use similar type.	
Total Bid:	



New Orleans Education League  
 2424 N. Arnoult Rd.  
 Metairie, LA 70001  
 (504) 837-2700  
 www.hbanoel.org

Site: Betty Blvd, Marrero      **90 Day Timeframe** Company Name: \_\_\_\_\_

<b>DEN:</b>	
25. R&R approximately 440 SF of carpet	
26. R&R approximately 440 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
27. R&R approximately 440 SF of batt insulation – 6" – R19 – paper faced	
28. Seal, Prime, Paint approximately 440 SF of surface area (2 coats)	
29. Detach and reset approx. 84 LF of crown molding – 3 1/4"	
30. Seal, paint approx. 84 LF of crown molding, oversized, 2 coats	
31. Detach and reset ceiling fan and light	
32. Detach and reset recessed light fixture	
Total Bid:	

<b>HALLWAY:</b>	
33. R&R approximately 45 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
34. R&R approximately 45 SF of batt insulation – 6" – R19 – paper faced	
35. Seal, Prime, Paint approximately 45 SF of surface area (2 coats)	
36. R&R approx. 32 LF of crown molding – 5 1/4"	
37. Seal and paint approx. 32 LF of crown molding, oversized – two coats	
38. R&R attic entrance cover and trim	
39. Paint attic cover and trim	
40. R&R light fixture. Use similar type.	
Total:	

<b>UTILITY ROOM:</b>	
41. R&R approximately 36 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
42. R&R approximately 36 SF of batt insulation – 6" – R19 – paper faced	
43. Seal and paint approx. 36 SF of surface area – two coats	
44. R&R light fixture. Use similar type.	
Total:	



New Orleans Education League  
 2424 N. Arnoult Rd.  
 Metairie, LA 70001  
 (504) 837-2700  
 www.hbanoel.org

Site: Betty Blvd, Marrero **90 Day Timeframe** Company Name: \_\_\_\_\_

<b>BEDROOM 1:</b>	
45. R&R approximately 144 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
46. R&R approximately 144 SF of batt insulation – 6" – R19 – paper faced	
47. Seal and paint approx. 144 SF of surface area – two coats	
48. Detach and reset ceiling fan and light	
Total:	

<b>BEDROOM 2:</b>	
49. R&R approximately 144 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
50. R&R approximately 144 SF of batt insulation – 6" – R19 – paper faced	
51. Seal and paint approx. 144 SF of surface area – two coats	
52. Detach and reset ceiling fan and light	
Total:	

<b>BATHROOM 1:</b>	
53. R&R approx. 5 LF of ½" drywall up to 4' tall (wall behind toilet and vanity)	
54. Seal, prime, paint approx. 104 SF of surface area (3 coats) all walls	
55. R&R approximately 40 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING	
56. R&R approximately 40 SF of batt insulation – 6" – R19 – paper faced	
57. Seal and paint approx. 40 SF of surface area – two coats	
58. R&R approx. 7 LF of baseboards – 4 ¼"	
59. Seal and paint approx. 7 LF of baseboards – 2 coats	
60. Detach and reset vanity	
61. Detach and reset sink faucet	
62. Detach and reset toilet	
63. Detach and reset bathroom ventilation fan and heater	
Total:	

**This job will be completed within 90 days of contract signing.**

Company Representative Signature: \_\_\_\_\_ Total Bid: \_\_\_\_\_

Company Representative Name: \_\_\_\_\_ Date: \_\_\_\_\_