



New Orleans Education League
 2424 N. Arnoult Rd.
 Metairie, LA 70001
 (504) 837-2700
 www.hbanoel.org

Site: Buccola Ave, Jefferson **90 Day Timeframe** Company Name: _____

BIDDERS ARE RESPONSIBLE FOR THEIR OWN MEASUREMENTS. INACCURATE BIDS RESULTING FROM INACCURATE MEASUREMENTS ARE THE FAULT OF THE BIDDING CONTRACTOR.

| EXTERIOR: | Bid Amount |
|--|------------|
| 1. Detach and reset ornamental iron security door – Front door | |
| 2. R&R exterior door – metal – high grade – front door | |
| 3. Prime and paint door unit – exterior (per side) | |
| 4. Door lockset & deadbolt – exterior – premium grade | |
| 5. Remove approximately 25sq including felt, furnish and install approximately 29sq of composition shingle 25 year roofing including felt and nails as needed. Replace all stacks and jacks. Install proper drip edge. | |
| 6. Roof should be installed according to manufacturer guidelines and adhere to all appropriate parish codes. | |
| Total Bid: | |

| LIVING ROOM: | Bid Amount |
|--|------------|
| 7. R&R approximately 252 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING | |
| 8. R&R approximately 252 SF of batt insulation – 6" – R19 – paper faced | |
| 9. Seal, Prime, Paint approximately 252 SF of surface area (2 coats) | |
| 10. R&R Light fixture. Use similar type. | |
| Total Bid: | |

| DINING ROOM: | Bid Amount |
|--|------------|
| 11. R&R approximately 63 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING | |
| 12. R&R approximately 63 SF of batt insulation – 6" – R19 – paper faced | |
| 13. Seal, Prime, Paint approximately 63 SF of surface area (2 coats) | |
| 14. R&R approx. 35 LF of trim board. 1"x4" – installed (pine) – ceiling trim | |
| 15. Stain and varnish finish trim. Sand and seal. | |
| 16. Detach and reset light fixture | |
| Total Bid: | |



New Orleans Education League
 2424 N. Arnoult Rd.
 Metairie, LA 70001
 (504) 837-2700
 www.hbanoel.org

Site: Buccola Ave, Jefferson **90 Day Timeframe** Company Name: _____

| | |
|---|--|
| DEN: | |
| 17. R&R approximately 376 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING | |
| 18. R&R approximately 376 SF of batt insulation – 6" – R19 – paper faced | |
| 19. Seal, Prime, Paint approximately 376 SF of surface area (2 coats) | |
| 20. R&R approx. 90 LF of trim board. 1"x4" – installed (pine) – ceiling trim | |
| 21. Stain and varnish finish trim. Sand and seal. | |
| 22. R&R light fixture. Use similar type. | |
| 23. Detach and reset ceiling fan and light | |
| Total Bid: | |

| | |
|--|--|
| HALLWAY: | |
| 24. R&R approximately 64 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING | |
| 25. R&R approximately 64 SF of batt insulation – 6" – R19 – paper faced | |
| 26. Seal, Prime, Paint approximately 64 SF of surface area (2 coats) | |
| 27. R&R light fixture. Use similar type. | |
| 28. R&R attic entrance cover and trim | |
| 29. Paint attic access cover and trim (2 coats) | |
| Total: | |

| | |
|--|--|
| UTILITY ROOM: | |
| 30. R&R approximately 24 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING | |
| 31. R&R approximately 24 SF of batt insulation – 6" – R19 – paper faced | |
| 32. Seal and paint approx. 24 SF of surface area – two coats | |
| 33. R&R light fixture | |
| Total: | |



New Orleans Education League
2424 N. Arnoult Rd.
Metairie, LA 70001
(504) 837-2700
www.hbanoel.org

Site: Buccola Ave, Jefferson **90 Day Timeframe** Company Name: _____

| | |
|---|--|
| BEDROOM 1: | |
| 34. R&R approximately 306 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING | |
| 35. R&R approximately 306 SF of batt insulation – 6" – R19 – paper faced | |
| 36. Seal and paint approx. 306 SF of surface area – two coats | |
| 37. Detach and reset ceiling fan and light. | |
| Total: | |

| | |
|--|--|
| BEDROOM 4: | |
| 38. R&R approximately 88 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING | |
| 39. R&R approximately 88 SF of batt insulation – 6" – R19 – paper faced | |
| 40. Seal and paint approx. 88 SF of surface area – two coats | |
| 41. R&R Light fixture. Use similar type. | |
| 42. Replace as needed, outlet/ switch cover | |
| Total: | |

| | |
|--|--|
| BATHROOM 1: | |
| 43. R&R approximately 90 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING | |
| 44. R&R approximately 90 SF of batt insulation – 6" – R19 – paper faced | |
| 45. Seal and paint approx. 90 SF of surface area – two coats | |
| 46. R&R bathroom ventilation fan, light, and heater | |
| Total: | |



New Orleans Education League
 2424 N. Arnoult Rd.
 Metairie, LA 70001
 (504) 837-2700
 www.hbanoel.org

Site: Buccola Ave, Jefferson **90 Day Timeframe** Company Name: _____

| | |
|--|--|
| BATHROOM 2: | |
| 47. R&R approx. 153 SF of ½" mold resistant drywall – hung, taped, floated, ready to paint. WALLS | |
| 48. Seal, prime, paint the surface area twice (3 coats) | |
| 49. R&R approximately 40 SF of 5/8" drywall – hung, taped, heavy texture, ready for paint. CEILING | |
| 50. R&R approximately 40 SF of batt insulation – 6" – R19 – paper faced | |
| 51. Seal and paint approx. 40 SF of surface area – two coats | |
| 52. Install new bathroom ventilation fan, light, and heater | |
| 53. R&R approx. 12 LF of baseboards 4 ¼" | |
| 54. Seal and paint baseboards - 2 coats | |
| 55. R&R vanity with cultured marble or solid surface top | |
| 56. Detach and reset bathroom mirror | |
| 57. R&R approximately 55SF of ½" cement board | |
| 58. Detach and reset toilet. Install complete with wax ring. | |
| 59. R&R tub/shower faucet – standard grade | |
| 60. R&R tile tub surround – up to 60 SF | |
| 61. Replace sink faucet – standard grade | |
| Total: | |

This job will be completed within 90 days of contract signing.

Company Representative Signature: _____ Total Bid: _____

Company Representative Name: _____ Date: _____