



Building Inspections for City of Wolfforth (as of May 1st)-
RESIDENTIAL ONLY

Order of Inspections:

1. Footing
2. Plumbing Rough and Service
3. Slab
4. SWPPP Inspection (this will not be called in, but completed)
5. **Framing- this will include plumbing top out, partial gas, mechanical rough, temp heat if required, and electrical rough** 
6. Electrical Meter Release (must be done before final)
7. **MEP Finals** 
8. CSI Inspection (this is done by our Public Works Department)
9. Final Building Inspection

***Bold are changes. These inspections will be grouped together.**

For any questions, please contact:

Kimberlea Groves
kgroves@wolfforthtx.us
806-855-4134

Call-in Example: Frame and Subs

The builder is responsible for scheduling all required inspections, including plumbing top-out, partial gas, mechanical rough, temporary heat (if needed), electrical rough, and framing. Before calling for an inspection, the builder must ensure that all trades are ready.

Call-in Example: MEP Finals

The builder is responsible for scheduling all final inspections for Mechanical, Electrical, and Plumbing (MEP) systems at the same time, but this does not include the final building inspection.

RED TAGS AND REINSPECTIONS: If any of these trades fail the inspection, only the specific trade that did not pass will receive a red tag. A re-inspection must then be scheduled for that trade to address the issues before approval is granted. During framing when the failed inspection is rescheduled, a framing inspection will also be included.